

08 January 2009

**BID PACKAGE A - SITE PREPARATION
THE GIVING TREE CHILDCARE CENTER, INC.
CLARKSVILLE, TN**



ADDENDUM NO. ONE

TO PLANHOLDERS: This addendum is issued to modify the original drawings, and is hereby made part of the contract documents. Please attach this addendum to the drawings in your possession. Review changes to each portion of the work, as changes of one portion may affect the work of another.

ITEM 01.

SECTION 01 11 00 - SUMMARY OF WORK; Delete page in its entirety and substitute the attached therefor.



END OF ADDENDUM NO. ONE

SECTION 01010 - SUMMARY OF WORK

PART 1 - GENERAL

PROJECT DESCRIPTION

The project consists of, but is not limited to, demolition, clearing, earthwork, retaining walls, drainage improvements and utility work as described in the Bid Documents. Demolition includes removal of a delapidated house, barn, appurtenances and other existing improvements above and below grade. Clearing includes removal of selected trees, brush and grubbing. Earthwork includes stripping and stockpiling of topsoil, excavation, borrow fill, compaction and grading. Retaining walls include precast concrete units and related trenching, bedding and backfill. Drainage improvements include underground stormwater piping, catch basin, and headwall systems, riprap and related work. Utility work includes replacement water main, sanitary sewer lift station and related work.

Specifically excluded from the Project are items identified as "Not In Contract" or "N.I.C.".

CONTRACTOR USE OF PREMISES

General:

Limit use of the premises to construction activities in areas where construction is indicated.

Confine operations to areas within the immediate areas of construction. Portions of the site beyond areas in which construction operations are indicated are not to be disturbed.

Schedule deliveries to minimize space and time requirements for storage of materials and equipment on site.

No work is to be performed on adjoining properties.

MANDATORY SEQUENCING OF WORK

General:

Erosion control measures shall be in place prior to commencing demolition and earthwork operations.

Temporary construction entrance shall be in place prior to commencing demolition and earthwork operations.

Replacement water main shall be operational before removal of existing water main.

PART 2 - PRODUCTS - Not applicable.

PART 3 - EXECUTION - Not applicable.

END OF SECTION 01010